

RFP #137-2024 Sidewalk and Curbs

Addendum #1 – July 23, 2023

Are you looking for unit prices or lump sum per bullet point?

Lump sum per bullet point

Is the area around the tennis court the highlighted area on the bid or just 245 LFT?

Highlighted area

Additional requirement: Please add Option B to all 3 locations, not just Tennis Courts Sidewalk at Rocketship Park. We would like to compare stamped concrete vs. re-use and replace existing brick at all locations.

Part B alternate

- Remove wooden border from brick sidewalks
- Remove brick walkways to be reused
- Excavate 4" in preparation for RCA to be compacted prior to installation of RCA
- Install 4" NY State spec RCA and compact with vibrating roller
- Install 6x610 wire
- Pour 4" thick concrete 4,000 psi
- Install existing bricks for walkway
- Clean up job site